| Requirement | Verification Type | Method |
|-------------------------------------------------------------------|-------------------|--------------------------------------------------------------------------|
| 1) The system shall detect when a person enters the monitored | Demonstration | Build video will show a person entering the room and being detected |
| room. | | by the system. |
| 2) The system shall detect when a person exits the monitored | Demonstration | Build video will show a person exiting the room and the count being |
| room. | | updated. |
| 3) The system shall maintain, update, and display a running | Test | System will be tested with multiple entries and exits, showing correct |
| count of the number of occupants in the room. | | running count in the build video. |
| 4) The system shall indicate occupancy levels using distinct | Test | System will be tested with varied occupancies and the correct LED |
| visual cues corresponding to empty, low, medium, high, and full | | indicator response will be recorded in the build video. |
| occupancy, as required by the customer. | | |
| 5) The system shall restrict entry once the occupancy limit is | Inspection | Code submission will show configurable limit. Build video will |
| reached. This limit shall be configurable by the system operator. | | demonstrate access denial when capacity is full. |
| 6) The system shall verify user health status prior to allowing | Demonstration | Build video will show user verification of health prior to entry through |
| entry, using a contactless or user-initiated method. | | the chosen method. |
| 7) The system shall simulate door control by indicating whether | Demonstration | Build video will show LED/door simulation behavior indicating grant or |
| entry is granted or denied. | | denial of entry. |
| 8) The system shall allow unrestricted exit from the room at all | Demonstration | Build video will show that users are always able to exit without any |
| times. | | restriction. |
| 9) The system shall maintain an accurate count of current room | Test | System will be tested with multiple entry/exit scenarios to validate |
| occupants throughout operation. | | real-time accuracy in build video. |
| 10) The system shall provide confirmation to the user when | Demonstration | Build video will show visual confirmation (e.g., door opening or LED) |
| entry is granted following a valid health verification. | | provided after successful health check. |